SHIMOGA DIVISION.

Notice dated 12th August 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 27th August 1928, for restoring the Arahatolalu Kakamallanakere registered No. 311 of Shimoga Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the 15th June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rupees ..... in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Arahatolalu Kakamallanakere Regd. No. 311 of Shimoga Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Shimoga Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for restoring Arahatolalu Kakamallanakere, major tank Registered No. 311, Shimoga Taluk.

Sl. No.	Items of work	Per	Quantity
	I. *Bund R. L.* 55·00 *width* 4½ *feet.*		
1	Jungle clearing over bund and right waste weir and cutting steps.	Lump sum	
2	Earthwork to bund including watering and tamping etc., complete.	C.yds.	10,977
3	Gravelling over the bund with one mile lead ...	,,	193
4	Turfing	S.ft.	81,783
5	Providing grade stones	No.	26
6	Do Index stones	,,	26
7	Do B. M. stones	,,	2
8	Do Guage stone	,,	1
9	Do Register number stone	,,	1
10	Do Date stone	,,	1
	II. *Sluice No.* 1 *at R. L.* 46·00.		
1	Earthwork cutting the bund and refilling the same with watering and tamping.	C.yds.	9
2	Earthwork excavation	,,	5
3	Surki concrete for foundation	C.ft.	14
4	Burnt brick in surki mortar	,,	248
4 (*a*)	or burnt stone in surki mortar	,,	248
5	Burnt stone slabs 3 ' thick dressed and fixed ...	S.ft.	66
6	Plastering with surki mortar	Sqr.	0·74
7	C. I. pipes 9" diameter including carting to site and fixing, etc., complete.	Rft.	27
8	Teakwood plug with iron rod with locking arrangements, etc., complete.	Lump sum	
9	Cutting grooves in orifice and gibbet slabs ...	,,	,,

Sl. No.	Items of work	Per	Quantity
	III. *Sluice No. 2 at R. L.* 45·00.		
1	Cutting bund and refilling the same with watering and tamping.	C.yds.	16
2	Earthwork excavation	,,	5
3	Surki concrete for foundation	C.ft.	14
4	Burnt brick in surki mortar	,,	279
4 (*a*)	or burnt stone in surki mortar	,,	279
5	Burnt stone slabs 3" thick dressed and fixed ..	Sft.	66
6	Plastering with surki mortar	Sqr.	0.78
7	C. I. pipes 9" diameter including carting to site and fixing, etc., complete.	Rft.	27
8	Teakwood plug with iron rod and with locking arrangements, etc., complete.	Lump sum	
9	Cutting grooves in orifice and gibbet slabs ...	,,	,,
	IV. *Waste weir Right* R. *L.* 50·00 *Length* 60 *feet.*		
1	Clearing approaches in front and using the same for bund.	C.yd	210
2	Earthwork excavation	,,	95
3	Surki concrete for foundation...	C.ft.	120
4	Burnt brick in surki mortar	,,	543
4 (*a*)	or Burnt stone in surki mortar	,,	543
5	Plastering with surki mortar	Sqrs.	5·88
6	Burnt stone slabs 6" thick dressed and fixed ...	S.ft.	116
7	Rough stone apron new	C.yds.	55
8	Providing joggles	Each	10
	V. *Wasteweir left R. L.* 50·00 *Length* 60 *feet.*		
1	Clearing draft and approaches and using for bund	C.yds.	210
2	Earthwork excavation	,,	87
3	Surki concrete for foundation	C.ft.	120
4	Burnt brick in surki mortar	,,	543
4 (*a*)	or Burnt stone in surki mortar	,,	543
5	Plastering with surki mortar	Sqrs.	5·88
6	Burnt stone slabs 6" thick dressed and fixed ...	S.ft.	116
7	Rough stone apron new	C.yds.	55
8	Providing joggles	Each	10

Notice dated 11th August 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 27th August 1928, for constructing a Maszid at Bhadravati. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 15th June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Governmen Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Maszid at Bhadravati," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer Shimoga Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond: in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for constructing a Maszid at Bhadravati, Shimoga Taluk.

No.	Items of work	Per	Quantity
1	Earthwork	C.yds.	91
2	Concrete in chunam	C.ft.	610
3	Stone in mortar	,,	1,520
4	Burnt brick in clay	,,	890
5	Burnt brick in mortar	,,	487
6	Brick in mortar arch work	,,	51
7	Teakwood panelled door 1½" thick shutters	S.ft.	84
8	Teakwood windows panelled shutters with ¾" iron bars ...	,,	54
9	Iron trusses	Cwt.	14
10	Teakwood work wrought and put up	C.ft.	57·11
11	Burnt stone slabs roughly dressed	S.ft.	80
12	Roofing with first class Mangalore tiles, etc.	Sqr.	8·32
13	Ridge tiles set in mortar	R.ft.	82
14	9" cornice work	,,	115
15	Ornamental parapet wall on the rear side	,,	6
16	Teakwook finials	Each	2
17	Cuddapah slabs flooring over 3" concrete	Sqr.	6·39
18	Chunam plastering	,,	24·50
19	White and colour washing	,,	24·50
20	Ordinary painting	,,	3·76
21	Heavy ornamental parapet wall	R.ft.	12
22	Ordinary parapet wall	,,	18
23	Building terrets and other ornamental works	L. S.	...

M. A. SRINIVASACHARI,
Executive Engineer.

SPECIAL DIVISION MYSORE.

Abstract Notification dated August 1928.

Attention of the public is invited to the Notifications published on pages 803-805 of Part VI, of the *Mysore Gazette*, dated 16th August 1928, calling for tenders for constructing Physiology Block and constructing Dis-section Theatre" attached to the Medical College at Mysore. The last date for presentation of the tenders is 3rd September 1928.

V. V. KARVE,
Executive Engineer.

MEDICAL DEPARTMENT.

VICTORIA HOSPITAL, BANGALORE.

TENDER NOTICE.

1. Notice is hereby given that sealed tenders in triplicate on half sheet foolscap size paper, will be received at the Office of the Victoria Hospital, Bangalore, by the undersigned at 11 A M., on Wednesday the 26th September 1928, for the supply of articles of Bedding and Clothing required for the use of the said Hospital.

2. No tenders will be received after the date and hour abovementioned.

3. Tenders to be superscribed "Tenders for the supply of Bedding and Clothing to the Victoria Hospital."

4. No tender will be received unless accompanied by a deposit of Rs. 200 in cash or currency notes or Treasury Receipts.